Existing informal access to be formalised. Existing parking bay and kerbs to be removed to accommodate.

Existing central island modified to accommodate pedestrians and cyclists

Proposed 'Toucan' crossing

Existing right-turn facility to be extended by 60m, to allow an additional 12 vehicles to wait

1.5m segregated cycleway to be constructed through area of foliage.

Footway to be widened by 1.0m.

Existing central island to be removed and give way markings adjusted, to accommodate cycle access to off-carriageway facility.

Existing pedestrian refuge to be removed to accommodate extended right turn lane

Proposed 'Toucan' crossing. See Inset B for details

Proposed pedestrian crossing, to be incorporated into existing traffic signals

End of shared-use

Nursery

Gilberts Lodge

1 to 15

1 to 15

Gilberts Lodge

BARRIERS ROAD

KILN LANE

KILN LANE

EAST STREET

EAST STREET

50.9m

50.3m

BM 50.91m

Shelter

LB

WINDMILL LANE

CHUTERS GROVE

Eole Court

TCB

MIDDLE CLOSE

0 50 100 150 200

Notes

East Street
Annex A

Rev.	Description	Drwn	Sig.	Date	Chkd	Sig.	Date	Appr	Sig.	Date

File Name

Scale NTS

North Point

'Based upon the Ordnance Survey mapping with the permission of the Controller of Her Majesty's Stationery Office © Crown copyright. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings.' Surrey County Council LA 076872 2003.

Drawn by SW	Sig.	Date Aug 10
Checked by originator	Sig.	Date
Approved by	Sig.	Date

Project: East Street shared use cycleway

Drawing: East Street / Kiln Lane junction & Kiln Lane toucan crossing

SHEET 1 OF 1

SURREY COUNTY COUNCIL
Environment
Head of Engineering
CMR Phillips
B.Sc., M.Sc., C.Eng., F.I.C.E

Project No.

Contract Sheet No.

Drawing No. –

Rev.

Classification FEAS

A3