

## ANNEXE D

### FLOODING & DRAINAGE SCHEMES 2008/09 BY DISTRICT/BOROUGH

PROJECT	FUNDING	VALUE	COMMENTS
<u>Elmbridge</u>			
South Road, Weybridge	LTP	40,000	Drainage system unable to cope with volume of water. Frequent flooding of properties.
<u>Epsom &amp; Ewell</u>			
<u>Mole Valley</u>			
Boxhill Road, Box Hill	LTP	40,000	Existing soakaway & drainage system to be investigated to understand cause of flooding.
Dorking Road, Leatherhead	LTP	75,000	Ponding on carriageway due to lack of positive drainage.
London Road, Westhumble	LTP	75,000	Ponding on carriageway due to profile of road & lack of positive drainage.

<u>Reigate &amp; Banstead</u>			
Gatton Bottom, Merstham	LTP	70,000	Reprofile of carriageway proposed to address ponding issues.
Downland Way, Tattenham	LTP	35,000	Soakaway improvement proposed to address flooding.
<u>Tandridge</u>			
Stanstead Road, Caterham	LTP	50,000	Existing soakaway not working. Alternative solutions being investigated.
Bletchingley Road, Godstone	LTP	40,000	Existing outfall pipe in poor condition to be replaced.
Racecourse Road, Dormansland	LTP	65,000	Flooding caused by insufficient drainage. Improvements to be investigated.