

Highways reconstruction and drainage works

	Main Access Rd	Gyratory System
Road Surface	Major weaknesses in road base, requires full reconstruction. Cost £90,000	No major weaknesses identified, minor patching and water proof only £10,000
Footway	Major weakness in key sections require full reconstruction Cost £20,000	No issues identified
Drainage	Potential system weakness with capacity not complying with current highway standards. However, review confirms no immediate risk of failure and thus recommends deep clean only, with ongoing risk monitored Cost £5,000	Existing drainage systems not connected as single unit, requires new pipes to connect all gullies into single system to remove ongoing risk of surface water £25,000
Streetlights	Lights recently upgraded as part of PFI upgrade, no issues identified	Lights recently upgraded as part of PFI upgrade, no issues identified
Total	£115,000	£35,000

Financial contribution breakdown by organisation

Organisation	Funding Contribution
SCC Grant Contribution	£110,000
Mole Valley District Council	£25,000
Kier Grant Contribution	£15,000
Total	£150,000

This page is intentionally left blank