EXISTING FOOTPATH TO BE WIDENED TO A WIDTH OF 3.0m TO INTRODUCE NEW SHARED FOOTPATH OVER A LENGTH OF APPROXIMATELY 220m - DRAINAGE ALTERATIONS WILL BE REQUIRED.

EXISTING PAIR OF ROAD CUSHIONS TO BE REMOVED - PROPOSED 1 No. NEW ROAD CUSHION TO BE INSTALLED TO SUIT NEW ROAD LAYOUT.

NEW ONE WAY SIGN TO DIAG.606 ON NEW ILLUMINATED 76mm WIDE BASED POST.

NEW ONE WAY SIGN TO DIAG.606 ON NEW ILLUMINATED 76mm WIDE BASED POST.

EXTENTS OF EXISTING ON-STREET PARKING TO BE INCREASED.

PROPOSED 1 No. NEW ROAD CUSHION AND 1 No. NEW CYCLE BY-PASS ISLAND TO BE INSTALLED TO SUIT NEW ROAD LAYOUT.

EXTENTS OF EXISTING TAXI RANK TO BE INCREASED.

PROPOSED NEW DROPPED KERBS OVER ACCESS DRIVEWAY.

PROPOSED NEW DROPPED KERBS OVER ACCESS DRIVEWAY.

NEW ONE WAY SIGN TO DIAG.606 ON NEW ILLUMINATED 76mm WIDE BASED POST.

EXISTING PAIR OF ROAD CUSHIONS TO BE REMOVED - PROPOSED 1 No. NEW ROAD CUSHION TO BE INSTALLED TO SUIT NEW ROAD LAYOUT.

PROPOSED 2.0m WIDE ON-CARRIAGEWAY CYCLE CONTRA-FLOW SYSTEM WITH 1.0m TAPERED CENTRAL HATCHING TO SUIT.

EXISTING PAIR OF ROAD CUSHIONS AND CENTRAL ISLAND TO BE REMOVED - PROPOSED 1 No. NEW ROAD CUSHION AND 1 No. NEW CYCLE BY-PASS ISLAND TO BE INSTALLED TO SUIT NEW ROAD LAYOUT.

NEW ONE WAY SIGN TO DIAG.606 ON NEW ILLUMINATED 76mm WIDE BASED POST.

PROPOSED 2.0m WIDE ON-CARRIAGEWAY CYCLE CONTRA-FLOW SYSTEM WITH TAPERED CENTRAL HATCHING TO SUIT.

DOUBLE YELLOW LINES TO BE INSTALLED THROUGHOUT PROPOSED ONE-WAY SYSTEM.

NEW 'NO ENTRY' SIGN TO DIAG.616 ON NEW 76mm POST.

NEW ONE WAY SIGN TO DIAG.606 ON NEW ILLUMINATED 76mm WIDE BASED POST.

EXISTING PEDESTRIAN REFUGE FACILITY TO BE REMOVED - PROPOSED 2.0m WIDE PEDESTRIAN REFUGE FACILITY TO BE INSTALLED TO SUIT NEW ROAD LAYOUT WITH NEW BACK TO BACK 'NO-ENTRY' SIGN TO DIAG.616 AND MINI ROUNDABOUT SIGN TO DIAG.611.1.

NOTE:

A REVIEW OF THE EXISTING ROAD MARKINGS ALONG THIS SECTION OF GRESHAM ROAD IS REQUIRED, ALONG WITH ADDITIONAL ROAD MARKINGS TO SUIT NEW PROPOSED ROAD LAYOUT.

A REVIEW OF THE EXISTING SIGNS ALONG THIS SECTION OF GRESHAM ROAD IS REQUIRED, ALONG WITH ADDITIONAL WARNING AND REPEATER SIGNS TO SUIT NEW PROPOSED ROAD LAYOUT.

Notes

Rev.	Description	Drwn	Sig.	Date	Chkd	Sig.	Date	Appr	Sig.	Date

File Name: \\EAV\PCatt\Resource Pool\Projects\NE Spelthorne\PC1003 Gresham Road, Staines\6. Drawings\Current\PC1003_04 & 05 Gresham Road Staines - One-Way System.dwg

Scale

North Point

"Based upon the Ordnance Survey mapping with the permission of the Controller of Her Majesty's Stationery Office © Crown copyright. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings." Surrey County Council LA 076872 2002.

Drawn by CHB	Sig. CHB	Date MAR 20
Checked by originator AP	Sig. AP	Date MAR 20
Approved by	Sig.	Date

Project: GRESHAM ROAD, STAINES UPON THAMES

Drawing: ONE-WAY SYSTEM

SHEET 1 OF 2

SURREY COUNTY COUNCIL

Project No. PC1003

Contract Sheet No.

Drawing No. PC1003_04 Rev. -

Classification PRESENTATION

A3

This page is intentionally left blank